Sunshine Roofing

90 Birch st. Roslindale M.A. P: 8572515826 jlamy211@gmail.com



Bill To

Tim Mckenna mckennatim@gmail.com

Estimate EST0030

Date 05/29/2019

DESCRIPTION	QTY	RATE	AMOUNT
Install new Rubber Roofing system		\$15,000.00	\$15,000.00
1. Supply dumpster and necessaey equipment			
Remove existing rubber roof and damaged insulation dispose of in dumpster			
3. Also remove all ventilation from same roof Install 1 inch iso board with plates and screws over decking and cover with 060 commercial rubber roofing membrane			
4. Install new drain pain flash to new roof			
5. Install new metal trim on perimiter of building Flash chimney and cast iron vents using new required EPDM flashing system			
Clean job site guarantee new roof for 10 years			
New ventilation system Remove all old roofing vents. Install new roofing vents along with new roof and flash with EPDM flashing.		\$1,050.00	\$1,050.00

Payment instructions Total \$16,050.00

By check

Make checks payable to: Sunshine Roofing

05/29/2019